

GENERAL NOTES:

A. COORDINATE DEMOLITION SEQUENCE WITH CONSTRUCTION PHASING TO ENSURE EXISTING GENERATOR POWER IS NOT REMOVED UNTIL NEW GENERATOR SYSTEMS ARE INSTALLED.

B. THE ELECTRICAL DRAWINGS SHOW ALL EXISTING ELECTRICAL EQUIPMENT AND SYSTEMS AS CAN BE VIEWED OR AS INDICATED ON PREVIOUS CONTRACT DOCUMENTS AVAILABLE. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS TO DETERMINE THE ENTIRE EXTENT OF EXISTING ELECTRICAL SYSTEM EQUIPMENT AND CONTROLS. THESE DRAWINGS SHOW DEMOLITION WORK THAT WILL BE COMPLETED IN TOTAL FOR ALL CONSTRUCTION PHASES, NOT JUST FOR THIS WP-1 SCOPE OF WORK. THIS CONTRACTOR SHALL LEAVE ALL EXISTING ELECTRICAL SYSTEM EQUIPMENT AND CONTROLS THAT ARE NECESSARY TO SERVE THE OCCUPIED BUILDING AREAS DURING WP-1, REMOVING ONLY THAT WHICH IS NECESSARY FOR WP-1 DEMOLITION.

C. CONTRACTOR SHALL FIELD VERIFY EXACT CONDITIONS PRIOR TO ANY DEMOLITION. ELECTRICAL CONTRACTOR SHALL MAINTAIN CONTINUITY OF ADJACENT CIRCUITS TO DEVICES OR EQUIPMENT THAT ARE TO REMAIN DURING CONSTRUCTION. REROUTE CONDUIT AND WIRING AS NECESSARY.

D. ELECTRICAL DEVICES AND EQUIPMENT SHOWN AS DASHED ARE TO BE DEMOLISHED AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DISPOSE OF UNLESS NOTED OTHERWISE. ELECTRICAL DEVICES/EQUIPMENT SHOWN WITH LIGHT SOLID LINE TYPE ARE EXISTING TO REMAIN. ANY ITEMS TO BE TURNED OVER TO FACILITIES MANAGEMENT WILL BE NOTED.

E. EQUIPMENT SHOWN HATCHED IS TO BE DISCONNECTED AND REMOVED. COORDINATE REMOVAL OF EQUIPMENT WITH APPROPRIATE WORKPACKAGES.

KEYNOTES:

1. INTERCEPT EXISTING FEEDER AT MANHOLE 21. REFER TO SITE PLAN E130. MODIFY AND EXTEND FEEDERS AS NECESSARY SHOWN ON E014.

2. INTERCEPT EXISTING FEEDER. MODIFY AND EXTEND FEEDER AS NECESSARY. REFER TO E012 FOR NEW POWER SOURCE.

3. TRACE CONDUIT TO ADMINISTRATION BUILDING. VERIFY IF FEEDER EXISTS AND SUPPORTS EQUIPMENT. COORDINATE EXISTING ROUTE AND REMOVAL WITH ENGINEER.

